

SCOPE OF WORK & TECHNICAL SPECIFICATION

Project: Jeddah Mall Renovation – Phase 2
Document Ref: JMR-SOW-2025-02 | Issue Date: 10 March 2025

1. PROJECT OVERVIEW

The Jeddah Mall Renovation – Phase 2 project comprises a comprehensive interior renovation, MEP upgrade, and façade refurbishment of the existing four-storey shopping mall located on Tahlia Street, Jeddah. The renovation covers a total gross floor area of approximately 42,000 square metres and is intended to modernise tenant spaces, upgrade engineering services to current Saudi Building Code (SBC) standards, and reposition the mall as a premium retail destination.

The Works shall be carried out under a phased programme with the mall remaining partially operational during weekends. The Contractor shall coordinate all noisy and disruptive works to be carried out outside mall trading hours (10:00 PM to 8:00 AM).

2. PROJECT OBJECTIVES

- Modernise mall interiors with contemporary finishes aligned with international retail standards.
- Upgrade HVAC systems to achieve LEED Silver certification.
- Replace existing single-glazed façade with energy-efficient double-glazed unitised system.
- Install new high-speed escalators and panoramic elevators throughout common areas.
- Re-design food court and entertainment zones to increase tenant capacity by 35%.
- Implement a centralised Building Management System (BMS) integrated with security and fire systems.

3. DETAILED SCOPE OF WORK

3.1 Demolition and Strip-Out Works

The Contractor shall undertake selective demolition of existing internal partitions, suspended ceilings, floor finishes, doors, and joinery. All asbestos-containing materials, if encountered, shall be handled in accordance with Royal Commission for Jubail and Yanbu (RCJY) Environmental Regulations and disposed of at licensed facilities. Approximately 8,500 m² of suspended ceiling, 12,400 m² of floor finishes, and 3,200 linear metres of partitions are to be removed.

3.2 Structural Works

Localised structural reinforcement is required at the second-floor slab to accommodate the new food court loading. This includes carbon fibre reinforced polymer (CFRP) strengthening of selected beams, installation of new steel transfer beams at grids C-7 to C-11, and core-cutting of new mechanical openings. All structural modifications shall be designed by a Saudi Council of Engineers (SCE) registered Structural Engineer and approved by Jeddah Municipality.

3.3 Mechanical, Electrical and Plumbing (MEP)

The MEP scope encompasses the following systems:

- **HVAC:** Replacement of existing 1,800 TR chiller plant with two new 1,200 TR magnetic-bearing chillers; new VAV air distribution; new AHUs serving each tenant zone with VFD control.
- **Electrical:** Upgrade of main LV switchgear from 4,000A to 6,300A; installation of new 1,250 kVA standby generator; full LED lighting retrofit with DALI controls.

- **Plumbing:** Replacement of all domestic water risers; new pressure-zoned distribution; installation of greywater recycling system serving all WCs.
- **Fire Safety:** Full sprinkler system upgrade in line with NFPA 13; new addressable fire alarm system; voice evacuation; smoke management system.
- **Vertical Transportation:** Replacement of 12 existing escalators and installation of 4 new panoramic glass elevators.
- **BMS:** Centralised graphical front-end integrating HVAC, lighting, energy metering, fire alarm, and access control.

3.4 Façade Works

The existing aluminium and single-glazed façade shall be replaced with a new unitised curtain wall system comprising 6mm + 12mm air gap + 6mm laminated low-E double glazing, with a U-value not exceeding 1.6 W/m²K and a Solar Heat Gain Coefficient (SHGC) of 0.28 or lower. Total façade area is approximately 11,500 m². The Contractor shall provide mock-up samples for approval prior to bulk fabrication and shall carry out CWCT performance testing to wind, water, and seismic standards.

3.5 Internal Finishes

- Floor: Polished porcelain tiles in mall walkways (1200x600mm), Italian marble at main atrium and entrances.
- Walls: Acoustic timber cladding in food court, decorative metal mesh in luxury zones, vinyl-wrapped panels at tenant fronts.
- Ceilings: Stretched fabric ceilings with backlit lighting in atrium; mineral fibre tiles in service areas.
- Joinery: Bespoke timber joinery for information desks, customer service kiosks, and prayer rooms.

4. KEY DELIVERABLES

Deliverable	Due Date	Format
Detailed Design Package	15 April 2025	PDF + DWG + Revit
Construction Programme (Primavera P6)	30 April 2025	XER + PDF Gantt
Material Submittal Register	15 May 2025	Excel + Sample Boards
Method Statements & RAMS	01 June 2025	PDF Bound
Mock-up Approvals (Façade & Finishes)	15 July 2025	On-site + Photo Log
Testing & Commissioning Plan	01 December 2025	PDF
As-Built Drawings	15 May 2026	DWG + PDF
O&M Manuals (4 hard copies + USB)	20 May 2026	Bound Volumes
Substantial Completion Certificate	30 May 2026	Signed

5. APPLICABLE STANDARDS AND CODES

- Saudi Building Code (SBC 201, 301, 401, 501, 601, 801) – latest editions
- NFPA 13 – Sprinkler Systems
- NFPA 72 – Fire Alarm and Signaling Code
- ASHRAE 90.1 – Energy Standard for Buildings
- ASHRAE 62.1 – Ventilation for Acceptable Indoor Air Quality
- BS EN 14351 – Window and Door Performance Standards
- CWCT Standard for Curtain Walling
- Saudi Arabian Standards Organization (SASO) regulations for electrical equipment
- OSHA-aligned KSA Labour Law for HSE compliance

6. EXCLUSIONS FROM SCOPE

- Tenant fit-out works within demised retail units (by tenants directly).
- External road and infrastructure works beyond the property boundary.

- Permanent furniture, fixtures and equipment (FF&E;) for individual tenants.
- Procurement of art installations and decorative sculptures.
- Operations and maintenance services post-handover (covered under separate contract).

7. HEALTH, SAFETY AND ENVIRONMENT (HSE)

The Contractor shall implement a comprehensive HSE management system aligned with ISO 45001 and ISO 14001. Minimum requirements include a full-time NEBOSH IGC qualified HSE Manager, dedicated first-aid stations on each level, weekly HSE inductions for all site workers, and monthly third-party HSE audits. The target incident rate is zero Lost Time Injuries (LTI) over the project duration, with a maximum acceptable Total Recordable Incident Rate (TRIR) of 0.5 per 200,000 man-hours.